

STANDARD FEATURES

- Solid one-piece cast marble
- Durable gel coat surface
- Pre-leveled-rests on subfloor
- Extremely sanitary
- Will not mold or mildew
- Easy to install
- Maintenance-free
- · Manufactured in the U.S.A.
- Recommended: add Shower Pan Liners to protect pans during construction


TECHNICAL SPECIFICATIONS

APPLICATIONS

• Hospitality | Multifamily | Senior Living | Student Housing | Military Housing

ITEM NUMBER

• SP-3660-10inOS-SF





MODEL Offset Drain Pan PAN SIZE 36" x 60" MATERIAL Cast Marble FLOOR PATTERN Traditional **FINISH** Matte, Textured, Non-Slip **BACKWALL** 59 7/8" SIDE WALLS 36" **DRAIN LOCATION** 10" Offset - (specify left or right) CENTER OF DRAIN MEASURES 18" from backwall, 10" from side wall DIMENSIONS NOTE: Finished product dimensions may vary +/- 1/8" from drawings **DRAIN OPENING** 3 1/4" FRONT CURB Integral - 3" w x 3" h **FLANGE** 1" on side and backwalls attached at factory WEIGHT ~ 304# **STANDARD** Mincey Classic™ SLOPE Pan is sloped toward the drain at 2% CSI NUMBER 22 42 23

CONTACT OUR SALES STAFF M-F: 8:00 am - 5:00 pm Eastern

770-532-0451



Request a product sample, color sample or get a quote.

sales@minceymarble.com samples@minceymarble.com

COLORS

ALMOND

BONE

7800

7670




CREAM	7400
IVORY	7300
WHITE	2250
LIGHT GRAY	7256
PUTTY	7000

SPECIAL NOTES

- Standards and Ratings:
- CSA B45-5/IAPMO Z124-2011
- MAS Certified Green. Compliant with ANSI/BIFMA X7.1 Standard
- ANSI A137.1 (average rating of 0.65)
- ANSI A326.3 (average rating of 0.72)
- ANSI/NFSI B101.3 (average rating of 0.66)
- Suggested Drains:
- Sioux Chief Mfg. model: 825-2P PVC
- Oatey part number: 42045 PVC
- Oatey part number: 42150 Brass
- NOTE: Finished product dimensions may vary +/- 1/8" from drawings
- NOTE: Drain is not included with pan




SP-3660-10"-OS/SF-L




Finished product dimensions may vary by +/- 1/8" from drawings.


SP-3660-10"-OS/SF-R




Finished product dimensions may vary by +/- 1/8" from drawings.



Integral 3" Curb





REV: 11.04.21